

**A. Bid Schedule Part 1 - SR 46 Detour Rd. Force Main and Sewer Relocations
(Financial Project No. 240216-5-56-01, SR 46 Detour Road Surcharge)**

	DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	TOTAL PRICE
SR 46 Detour Rd. Force Main and Sewer Relocations (FDOT Participating in Expense)					
A1	Mobilization	LS	1		
A2	Maintenance of Traffic	LS	1		
A3	Erosion and Sediment Control	LS	1		
A4	Silt Fence	LF	1711		
A5	Clearing and Grubbing	LS	1		
A6	Cut and Cap Existing 6" Force Main (Restrained Cap / Thrust Collar)	EA	3		
A7	Remove Existing 6" PVC Force Main	LF	1543		
A8	Cut and Plug Existing Sanitary Sewer	EA	1		
A9	Remove Existing Sanitary Sewer (15" and Smaller)	LF	525		
A10	Remove Existing Sewer Manhole	EA	3		
A11	Fittings (Force Main)	TN	0.17		
A12	Open Cut New 6" PVC Force Main	LF	1734		
A13	Open Cut New 10" PVC Sanitary Sewer	LF	396		
A14	Install New Sanitary Sewer Manhole	EA	4		
A15	Connect Existing Sanitary Sewer to New Sewer Manhole	EA	1		
A16	Connect New Sanitary Sewer to Existing Manhole	EA	1		
A17	6" x 6" Tapping Sleeve and Valve	EA	2		
A18	6" Plug Valve	EA	1		
A19	Air Release Valve (Offset)	EA	1		
A20	Open Cut Remove and Replace Existing Asphalt Maintenance Road	SY	202		
A21	Remove and Reinstall Existing Airport Perimeter Fence	LF	173		
A22	Install New 7' Chain Link Fence At Lift Station	LF	166		
A23	Install New Double Swing Gate (16' Opening) at Lift Station	EA	1		
A24	Hydroseeding	SY	7530		
SUB-TOTAL BASE BID PART 1					

**B. Bid Schedule Part 2 - SR 46 Detour Rd. Water Main Relocations
(Financial Project No. 240216-5-52-01, SR 46 Detour Road Surcharge)**

	DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	TOTAL PRICE
SR 46 Detour Rd. Water Main Relocations (At UAO's (City of Sanford's) Sole Expense)					
B1	Mobilization	LS	1		
B2	Maintenance of Traffic	LS	1		
B3	Silt Fence	LF	378		
B4	Clearing and Grubbing	LS	1		
B5	8" Line Stop	EA	4		
B6	Cut and Cap Existing 8" Water Main (Restrained Cap / Thrust Collar)	EA	4		
B7	Remove Existing 8" Water Main	LF	226		
B8	Remove Existing Fire Hydrant	EA	1		
B9	Fittings (Water Main)	TN	0.45		
B10	Open Cut New 8" DI Water Main (Restrained)	LF	297		
B11	8"x8" Tapping Sleeve and Valve	EA	4		
B12	Sodding (Bahia)	SY	903		
SUB-TOTAL BASE BID PART 2					

**C. Bid Schedule Part 3 - SR 415 Utility Relocations
(Financial Project No. 407355-1-52-01)**

	DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	TOTAL PRICE
SR 415 Utility Relocations (At UAO's (City of Sanford's) Sole Expense)					
C1	Mobilization	LS	1		
C2	Maintenance of Traffic	LS	1		
C3	Preconstruction Video	LS	1		
C4	Silt Fence	LF	590		
C5	Floating Turbidity Barrier	LF	30		
C6	Clearing and Grubbing	LS	1		
C7	Cut and Cap Existing 6" Force Main (Restrained Cap / Thrust Collar)	EA	5		
C8	Remove Existing 6" PVC Force Main	LF	860		
C9	Remove Plug and Connect to Existing 6" Force Main	EA	1		
C10	8" Line Stop	EA	2		

SR 46 Detour Rd. and SR 415 Utility Relocations
NAME OF BIDDER:

C11	Cut and Cap Existing 8" Reclaimed Water Main (Restrained Cap / Thrust Collar)	EA	4		
C12	Cut and Cap Existing 20" Reclaimed Water Main (Restrained Cap / Thrust Collar)	EA	2		
C13	Remove Existing 8" Reclaimed Water Main	LF	287		
C14	Grout in Place Existing 8" PE Reclaimed Water Main	LF	643		
C15	Remove Existing 20" Reclaimed Water Main	LF	112		
C16	10" Line Stop	EA	6		
C17	Cut and Cap Existing 10" Water Main (Restrained Cap / Thrust Collar)	EA	6		
C18	Remove Existing 10" Water Main	LF	226		
C19	Fittings (Force Main)	TN	0.66		
C20	Fittings (Reclaimed Water Main)	TN	2.55		
C21	Fittings (Water Main)	TN	1.00		
C22	Open Cut New 6" PVC Force Main	LF	887		
C23	Open Cut New 8" PVC Reclaimed Water Main	LF	960		
C24	Open Cut New 8" PVC Water Main	LF	86		
C25	New 8" Water Main (D.I.) (Restrained) (Installed Through Steel Casing)	LF	55		
C26	Open Cut New 10" PVC Water Main	LF	264		
C27	Open Cut New 20" PVC Reclaimed Water Main	LF	138		
C28	Jack and Bore 20" Steel Casing	LF	55		
C29	6"x6" Tapping Sleeve and Valve	EA	3		
C30	8"x8" Tapping Sleeve and Valve	EA	3		
C31	10"x8" Tapping Sleeve and Valve	EA	1		
C32	10"x10" Tapping Sleeve and Valve	EA	6		
C33	8" Gate Valve	EA	1		
C34	Cut Existing 20" Reclaimed Water Main, Install 20" 45 Degree Bend	EA	2		
C35	Air Release Valve (Offset)	EA	1		
C36	2" Blowoff Assembly	EA	1		
C37	Open Cut Remove and Replace Existing Asphalt Driveway	SY	38		
C38	Regrade Existing Ditch	LF	775		
C39	Sodding (Bahia)	SY	2514		
SUB-TOTAL BASE BID PART 3					

TOTAL BASE BID	
Part 1 - SR 46 Detour Rd. Force Main and Sewer Relocations	
Part 2 - SR 46 Detour Rd. Water Main Relocations	
Part 3 - SR 415 Utility Relocations	
TOTAL	

Note: Bidders must submit bid prices for all three (3) parts.

NOTE: PROVIDE ALL PAGES OF THE BID FORM AS PART OF THE BID SUBMITTAL.